

TRANSMITTAL SHEET

TO: All Bidders
DATE: April 16, 2021
TOTAL NUMBER OF PAGES (INCLUDING COVER PAGE): 5
FROM: Holly Young TEL. #: 506-658-2849
Utilities & Infrastructure Services

IF YOU DID NOT RECEIVE ALL PAGES, OR FURTHER INFORMATION IS REQUIRED,
PLEASE CONTACT THE SENDER

MESSAGE:

TENDER NO: 2021-06

**PRINCESS STREET (WENTWORTH STREET TO CROWN STREET) – WATER,
SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION**

Please find attached a copy of **Addendum #1** for the above tender.

As of March 2021, please be advised that an ***Acknowledgement Form*** (historically sent as part of the City's addendum packages) confirming receipt of an Addendum is **no longer** included in the addendum package.

However, in accordance with Section 2.5.03 of the City's General Specifications, it remains a requirement that **each Addendum** will contain a signature page(s) which each Tenderer is **required to sign and include with its Tender submission.**



UTILITIES & INFRASTRUCTURE SERVICES
 Engineering Services
 175 Rothesay Avenue
 Saint John, NB, E2J 2B4

ADDENDUM

PROJECT TITLE: PRINCESS STREET (WENTWORTH STREET TO CROWN STREET) – WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ADDENDUM NO: 1

DATE: _____

PAGE: 1 **OF** 4

TENDER NO: 2021-06

MAKE THE FOLLOWING MODIFICATIONS TO THE ABOVE PROJECT. INCLUDE IN THE AMOUNT OF THE TENDER ANY ADDITIONS TO OR DEDUCTIONS FROM THE COST OF THE WORK BY REASON OF THESE INSTRUCTIONS. THE DATE FOR RECEIVING TENDERS REMAINS AT: **2:30 PM, WEDNESDAY, APRIL 21ST, 2021.**

ADDITION TO THE SPECIFICATIONS

Division 2 – Submission of Tender

As a result of the COVID-19 pandemic, the City of Saint John is implementing adjustments to the tender submission procedure as follows:

Section 2.6.01 Location of Tender Box for the Submission of Tender

175 Rothesay Avenue, Saint John, New Brunswick

The tender box will be available at the main building entrance for submission of tenders by the Tenderer between the hours of 9:30 am and 2:30 pm only on the above tender closing date. Tenderers shall maintain physical distancing from others when depositing their tender in the tender box.

There will not be a public tender opening. Registered Bidders will receive an email invitation to view the Tender Opening using Microsoft Teams software. Email invitations will be sent to the address provided on the Official Bidder’s List. The Tender Opening Committee will conduct the evaluation of the Tenders and Compliant tenders will be included in the summary of bids on the City’s Tenders & Procurements website within 1 business day following the tender closing.

Division 3 – Particular Specifications

Section 3.1 – Additional Specifications for this Project

Replace the work Description with:

3.1.1 Work Description

On Princess Street (Wentworth Street to Crown Street), the Work consists generally of supplying all labour, materials and equipment for the excavation, installation, backfilling, commissioning and testing of watermain, sanitary sewer, storm sewer, services to the property lines, gate valves, fire hydrants, fittings, associated appurtenances, manholes, catch basins, curb reinstatement, sidewalk reinstatement and asphalt pavement. This work also includes the installation of four (4) laterals (2 storm and 2 sanitary) to Civic # 101-103 Pitt Street. Note the granite curb sections in front of Civic # 101-103 Pitt Street are to be re-used during reinstatement with this being considered incidental to the cost of the work.

More specifically, the project consists of the supply and installation of approximately:

- Water - 13 lineal metres of 150 mm diameter, 20 lineal metres of 200 mm diameter, 259 lineal metres of 250 mm diameter, and 14 lineal metres of 400 mm diameter watermain, service renewals, bends, fittings, valves and associated appurtenances;
- Sanitary – 289 lineal metres of 150 mm diameter and 275 lineal metres of 300 mm diameter sanitary sewer, service renewals and associated appurtenances;
- Storm – 66 lineal metres of 100 mm diameter, 88 lineal metres of 200 mm diameter, and 255 lineal metres of 300 mm diameter storm sewer and associated appurtenances;
- Curb and Sidewalk - 524 lineal metres of concrete curbing; and 712 lineal metres of concrete sidewalk;
- Road Reconstruction – 2,115 cubic metres of common excavation for road reconstruction; 1,140 cubic meters of imported pit-run gravel sub-base material and 500 cubic metres of crushed gravel base material for road reconstruction; 435 metric tonnes of Superpave 12.5 and 238 metric tonnes of Superpave 9.5; and
- Landscaping restoration and roadway signage.

This Project is to be completed in accordance with the 2020 City of Saint John General Specifications.

Division 4- Form of Tender

Section 4.5 – Schedule of Quantities and Unit Prices

Replace Sheets 8 of 18 AND 9 of 18 with the Revised sheets attached to this Addendum.

Note: Signed copy of the addendum must be enclosed in the tender documents, according to the Instructions to Tenderers and Tendering Procedures in Division 2 of the Contract Specifications.

BY:



CHIEF CITY ENGINEER

CONTRACTOR'S SIGNATURE

TO BE SIGNED AND ATTACHED TO TENDER DOCUMENTS

DIVISION 4

UNIT PRICE TO BE EITHER
TYPEWRITTEN OR PRINTED
IN INK IN WORDS AND
PRINTED NUMERICALLY

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2021-06

TITLE: PRINCESS STREET (WENTWORTH STREET TO CROWN STREET)

WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
C	STORM SEWER						
1	<u>Excavation</u>	13					
a)	Rock		m ³	429			
2	<u>Pipelaying & Jointing: Storm Sewer - 7, 11 Supply & Install</u>						
a)	100mm Ø PVC, DR35 with gasket or approved equal (Color - White)		m	66			
b)	200mm Ø PVC, DR35 with gasket or approved equal		m	88			
c)	300mm Ø PVC, DR35 with gasket or approved equal		m	255			
d)	100mm Ø PVC Cap		Each	4			
e)	300mm Ø PVC Cap		Each	1			
f)	Inlet Control Device for Catch Basin		Each	7			

DIVISION 4

UNIT PRICE TO BE EITHER
TYPEWRITTEN OR PRINTED
IN INK IN WORDS AND
PRINTED NUMERICALLY

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2021-06

TITLE: PRINCESS STREET (WENTWORTH STREET TO CROWN STREET)

WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
g)	Adjust connections into manhole or catch basin due to obstacles, etc.		Each	1			
h)	100mm storm sewer lateral connections to main (incl. fittings and bends typ.)		Each	7			
i)	Connection of new 100mm Ø pipe to existing 100mm Ø pipe incl. coupling		Each	3			
j)	Connection of new 200mm Ø pipe to existing 200mm Ø pipe incl. coupling		Each	1			
3	<u>Insulation - Supply & Install</u>	11					
a)	Supply and install 50mm thick insulation		m ²	6			
4	<u>Manholes & Catch Basins -Supply & Install</u>	12					
a)	1050mm Ø precast MH complete with City adjustable frame and cover and incl. all labour & materials necessary to connect to new and existing mains & laterals, etc.		Each	7			