

ADDENDUM

PROJECT TITLE: LANCASTER LAGOON BLOWER UPGRADE AND DO CONTROL	ADD. NO: 2
TENDER NO: 2022-085302T	DATE: November 8 th , 2022
PAGE 1 of 3 (Including Confirmation Sheet)	

Make the following modifications to the above project. Include in the amount of the Tender, any additions to or deductions from the cost of the work by reason of these instructions.

Sign and attach this Addendum to the Tender documents and submit with your Tender. Failure to do so may result in the rejection of your Tender.

Please note the following questions and answers.

- Q1. Please confirm that retaining blocks along roadway in area adjacent to proposed trench for DO Transmitter are to be removed /relocated by others in order to perform excavation and backfilling
- A1. Retaining blocks to be moved by the City.
- Q2. Please confirm route from Blower Building to DO Transmitter location can be modified from plan drawings in order to avoid the cutting and reinstatement of asphalt driveway
- A2. The DO transmitter is shown on the opposite side of the driveway from the Blower Building in both drawing E-1 and drawing P-01, driveway reinstatement is required. Alternate routing around asphalt will be considered but final trench location to be determined by SJW. Contractor shall carry costs for underground locates prior to trenching.
- Q3. Please confirm both Blower #1 and #5 replacements can be performed concurrently and the Facility has sufficient capacity with remaining blowers to operate facility
- A3. Blowers No. 1 and No. 5 replacements can be performed concurrently. Coordination with SJW is still required.
- Q4. Please confirm the existing VFD's for Blowers #1 and #5 shall remain in place after new Blowers have been installed and the removal of these will be by others
- A4. Blower No. 1 VFD will remain in place as a spare, see note 2, Detail 6 on Drawing E-2. Blower No. 5 does not currently have a VFD. VFD will remain in place, but all conduit

SIGN AND RETURN THIS ADDENDUM WITH YOUR PROPOSAL

BY: Monic Maelluar		
Monic MacVicar, CCLP, CPPB	Contractor's Signature	
Procurement Specialist, Supply Chain Management		



ADDENDUM

PROJECT TITLE: LANCASTER LAGOON BLOWER UPGRADE AND DO CONTROL	ADD. NO: 2
TENDER NO: 2022-085302T	DATE: November 8 th , 2022
PAGE 2 of 3 (Including Confirmation Sheet)	

and wire shall be removed. Existing lamicoids shall be replaced with new to state "Equipment not in use".

- Q5. Will owner require any portion of the scope of work to be performed during evenings or weekends?
- A5. SJW expects that when work disrupting air distribution to the cells is in process that it will be completed in one work session, for example installation of valves 1 through 6.
- Q6. Can you clarify if we have to include or not HST in our price?
- A6. Pricing shall <u>exclude</u> HST and shall be in Canadian funds.
- Q7. The existing overhead monorail does not appear to have the capacity to lift the specified equipment can you confirm that contractors should not use the monorail for moving/placing the new blowers?
- A7. Contractor should not assume to use SJW equipment to execute the project. Contractor to provide their own lifting/moving equipment.
- Q8. The new equipment pad detail (detail 3 on PO2) indicates the new pad should be coated to match existing.
- A8. Colour to match existing, coating PPG Aquapon 2 component epoxy at 2 to 3 mils DFT per coat, or equivalent.

Please add the following change to the drawing.

Drawing P04, delete item 2.11.2 and renumber subsequent items.

SIGN AND RETURN THIS ADDENDUM WITH YOUR PROPOSAL

BY: Monie Maelluar		
Monic MacVicar, CCLP, CPPB	Contractor's Signature	
Procurement Specialist, Supply Chain Management		



ADDENDUM

PROJECT TITLE: LANCASTER LAGOON BLOWER UPGRADE AND DO CONTROL	ADD. NO: 2
TENDER NO: 2022-085302T	DATE: November 8 th , 2022
PAGE 3 of 3 (Including Confirmation Sheet)	

CONFIRMATION - RECEIPT OF ADDENDUM

Upon receipt of this document, fax this page to (506) 658-4742 to confirm receipt of this addendum.

CONTRACTOR'S NAME:		
ADDRESS:		
PHONE:	FAX:	
RECEIVER NAME (PRINT)		
RECEIVER SIGNATURE:		