



ADDENDUM

PROJECT TITLE: SAINT JOHN POLICE HEADQUARTERS LIGHTING RETROFIT	ADD. NO: 2
TENDER NO: 2023-082303T	DATE: June 20 th , 2023
PAGE 1 of 3 (Including Confirmation Sheet)	

Make the following modifications to the above project. Include in the amount of the Tender, any additions to or deductions from the cost of the work by reason of these instructions.

Sign and attach this Addendum to the Tender documents and submit with your Tender. Failure to do so may result in the rejection of your Tender.

Please find below some clarification points/questions and answers.

Q1. Drawing E-1, General Note 4 – Can you confirm that this note applies to ceiling mounted occupancy sensors only?

A1. *Note 4 applies to all sensors.*

Q2. What are the hours of operation Drawing E-1, General Note 6 – Are we to assume that all fixtures being retrofitted do not already have a means of quick disconnect?

A2. *That is correct, we are unsure if they are equipped with disconnects presently. Price as though there are none presently.*

Q3. Drawing E-1, General Note 13 – Can you confirm that SJE will not need to be involved when shutting down the facility (contractor can shut down using facility breakers)? Can you confirm there are no costs associated with the involvement of the fire chief?

A3. *SJE has no need to be involved, we simply want to simulate a power outage to ensure the luminaires on emergency power turn on. Fire Chief does not need to get involved, this was a typo copied from another project involving Fire Stations.*

Q4. Drawing E-4 – Can you confirm that there is no work associated with the two type “V” fixtures shown on the exterior wall outside of the vehicle impound (room 1112)?

A4. *All exterior luminaires are existing LED type, no work required for the two Type V luminaires shown.*

Q5. Drawing E-4 – Can you advise on the requirements of fixture type “P1” shown just inside the door of forensics (room 1107)?

A5. *Type P1 is a typo, please provide a new Type ‘C1’ downlight.*

SIGN AND RETURN THIS ADDENDUM WITH YOUR PROPOSAL

BY: Monic MacVicar
 Monic MacVicar, CCLP, CPPB
 Procurement Specialist, Supply Chain Management

 Contractor’s Signature



ADDENDUM

PROJECT TITLE: SAINT JOHN POLICE HEADQUARTERS LIGHTING RETROFIT	ADD. NO: 2
TENDER NO: 2023-082303T	DATE: June 20 th , 2023
PAGE 2 of 3 (Including Confirmation Sheet)	

Q6. SKE-01, Specific Note 2 – Can you advise on a part number for the ceiling tiles that will need to be supplied? Does the Owner have spare stock that can be used?

A6. *Unsure if spare tiles are available, please match tiles as best as possible.*

Please find attached additional information from the architect.

SIGN AND RETURN THIS ADDENDUM WITH YOUR PROPOSAL

BY: Monic MacVicar
Monic MacVicar, CCLP, CPPB
Procurement Specialist, Supply Chain Management

Contractor's Signature



ADDENDUM

PROJECT TITLE: SAINT JOHN POLICE HEADQUARTERS LIGHTING RETROFIT	ADD. NO: 2
TENDER NO: 2023-082303T	DATE: June 20 th , 2023
PAGE 3 of 3 (Including Confirmation Sheet)	

CONFIRMATION - RECEIPT OF ADDENDUM

**Upon receipt of this document, fax this page to
(506) 658-4742 to confirm receipt of this addendum.**

CONTRACTOR'S NAME: _____

ADDRESS: _____

PHONE: _____ FAX: _____

RECEIVER NAME (PRINT) _____

RECEIVER SIGNATURE: _____



Addendum

120 Millennium Drive, Suite 201
Quispamsis, New Brunswick E2E 0C6
Phone (506) 847-8285 Fax (506) 848-2131
www.mcw.com

Date: June 20, 2023

Project Name: MBDER PKG #A13C – City of Saint John Police Headquarters - Lighting Retrofit

Client: City of Saint John

Project #: 12-22-076
Pkg A13C

To: City of Saint John - Supply Chain Management

ADD #: 2

Attention: Monic MacVicar

supplychainmanagement@saintjohn.ca

Page #: 1 of 1

From: Bob Cormier

Distribution: Samir Yammine – City of Saint John

Carman Travis - MCW

Louise Goguen - MCW

Tim Dulenty - MCW

In accordance with the drawings and specifications, provide in the tender all costs required to complete the work including items as listed below.

Title: Electrical
Reason for Change: Clarifications from Contractor Walk-Through

Electrical Drawings:

Drawing #	Revisions
E-6	<ul style="list-style-type: none"> • Reference Detail 1: Luminaire Schedule: <ul style="list-style-type: none"> • Reference Type C1D and C3D Luminaires: <ul style="list-style-type: none"> • Delete suffix "NLTAIR2" in Catalogue Number. • Reference Type "P" Measure: <ul style="list-style-type: none"> • Add note 6 as follows: <ul style="list-style-type: none"> • Provide a relay/power pack to control dimming ballast. Acuity Brand #rPP20D EFP

End of ADD # 2