

ADDENDUM

PROJECT TITLE: Equipment Installation – Thermal Interconnect	ADD. NO: 1
TENDER NO: 2023-085304T	DATE: October 25, 2023
PAGE 1 of 2 (Including Confirmation Sheet)	

Make the following modifications to the above project. Include in the amount of the Tender, any additions to or deductions from the cost of the work by reason of these instructions.

Sign and attach this Addendum to the Tender documents and submit with your Tender. Failure to do so may result in the rejection of your Tender.

Please see attached addendum from MCW Maricor.		

SIGN AND RETURN/THIS ADDENDUM WITH YOUR PROPOSAL

Chris Roberts, SCMP, CPPB Procurement Manager,

Supply Chain Management

Contractor's Signature



ADDENDUM

PROJECT TITLE: Equipment Installation – Thermal Interconnect	ADD. NO: 1
TENDER NO: 2023-085304T	DATE: October 25, 2023
PAGE 2 of 2 (Including Confirmation Sheet)	

CONFIRMATION - RECEIPT OF ADDENDUM

Upon receipt of this document, fax this page to (506) 658-4742 to confirm receipt of this addendum.

CONTRACTOR'S NAME:		
ADDRESS:		
PHONE:	FAX:	
RECEIVER NAME (PRINT)		
RECEIVER SIGNATURE:		



Addendum

 120 Millennium Drive, Suite 201
 Date: October 25, 2023

 Quispamsis, New Brunswick E2E 0C6
 Phone (506) 847-8285 Fax (506) 848-2131

www.mcw.com

Project Name: Canada Games Aquatic Centre

Saint John, NB

Interconnect from Market Square

Installation Package

Client: City of Saint John Project #: 12-23-012

To: City of Saint John ADD #: 1

Attention: Samir Yammine Page #: 1 of 2

From: Sigourney Stott sstott@mcw.com + Attachment

Distribution: Samir Yammine Steve Erb – MCW

Carman Travis - MCW

In accordance with the drawings and specifications, provide in the tender all costs required to complete the work including items as listed below.

Title: Additional information for concrete pads, electrical work and clarifications to drawings.

Reason for Change: Clarifications to scope of work.

Specifications:

Section #	Revisions
23 21 13	 Part 2, 2.1 PIPE: All piping shall be schedule 10 steel within Market Square and Canada Games Aquatic Center. Alternate piping solution for 100mm schedule 10 underground piping shall be Uponor Ecoflex PEX-a pre-insulated tubing solution. Plastic pipe shall not be permitted within the Market Square exhaust air shaft or within the Canada Games Aquatic Center basement mechanical room. Transition from PEX to schedule 10 steel within underground sleeve and fire stop at building penetration points.

Mechanical Drawings:

Drawing #	Revisions
M-1 / Grid J-10	The heat pump (HTHP-1) is supplied by owner and shall be installed by this contractor. This contractor is responsible for receipt of the heat pump at the Canada Games Aquatic Centre from the delivery truck. This contractor shall carry all costs to move HTHP-1 through the building to its final location in the basement mechanical room and complete installation.
M-1 & M-2	Contractor shall install concrete housekeeping pads for the following equipment. Pads shall be constructed as per detail MSK-3 (enclosed) and per the following dimensions:
M-3 Drawing 1	Provide fire sealing around pipe penetration to Market Square exhaust air shaft and Canada Games Aquatic Center basement mechanical room.



Project Name: Canada Games Aquatic Centre

Saint John, NB

Interconnect from Market Square

Installation Package

Client: City of Saint John

Project #: 12-23-012

ADD #: 1

Page #: 2 of 2

+ Attachment

Mechanical Drawings:

Drawing #	Revisions
M-4	 Contractor shall carry cost to purchase and install the following control valve on the HWRLT 150mm dia. piping leaving HX-1 located in the Market Square facility: Control Valve CV-1 acceptable product: Belimo G6150C+2*AFX24-MFT95-X1

Electrical Drawings:

Drawing #	Revisions
E-2	 Use of existing 150A breaker in panel 'DPS' in the Market Square is an acceptable alternate solution to feed the new 150A splitter in contract. If this method is pursued, feeder shall be changed to 1/0RW90 and a #6 bond.
E-4	 In the Canada Games Aquatic Center, the City of Saint John is currently completing installation of a 300A feeder from the main electrical room to the pump room. Feeder will be available for use by this contractor to complete the installation of the new panel "DP2). This contractor is not responsible for any work noted as "existing" on the single line diagram. Shark meter shall be complete with all accessories necessary to provide Modbus RTU connection.

End of ADD #1



