

TRANSMITTAL SHEET

TO: All Bidders

DATE: March 8, 2024

TOTAL NUMBER OF PAGES (INCLUDING COVER PAGE): 3

FROM: John Campbell, P. Eng. **TEL. #:** (506) 654-1354
Utilities & Infrastructure Services

IF YOU DID NOT RECEIVE ALL PAGES, OR FURTHER INFORMATION IS REQUIRED,
PLEASE CONTACT THE SENDER

MESSAGE:

TENDER NO: 2023-05

Dominion Park Road – Sanitary Lift Station Modifications

Please find attached a copy of **Addendum #1** for the above tender.

As of March 2021, please be advised that an ***Acknowledgement Form*** (historically sent as part of the City's addendum packages) confirming receipt of an Addendum is **no longer** included in the addendum package.

However, in accordance with Section 2.5.03 of the City's General Specifications, it remains a requirement that **each Addendum** will contain a signature page(s) which each Tenderer is **required to sign and include with its Tender submission.**



UTILITIES & INFRASTRUCTURE SERVICES

Engineering Services
175 Rothesay Avenue
Saint John, NB, E2J 2B4

ADDENDUM

PROJECT TITLE:

Dominion Park Road – Sanitary Lift Station Modifications

ADDENDUM NO:

1

DATE:

March 8, 2024

PAGE:

1

OF

2

TENDER NO:

2023-05

MAKE THE FOLLOWING MODIFICATIONS TO THE ABOVE PROJECT. INCLUDE IN THE AMOUNT OF THE TENDER ANY ADDITIONS TO OR DEDUCTIONS FROM THE COST OF THE WORK BY REASON OF THESE INSTRUCTIONS. THE DATE FOR RECEIVING TENDERS IS EXTENDED TO: **2:30PM, WEDNESDAY, MARCH 20, 2024.**

ADJUSTMENT TO THE SPECIFICATION**Division 2 – Submission of Tender**

The City of Saint John is implementing adjustments to the tender submission procedure as follows:

Section 2.6.01 Location of Tender Box for the Submission of Tender

175 Rothesay Avenue, Saint John, New Brunswick

The tender box will be available at the main building entrance for submission of tenders by the Tenderer between the hours of 9:30 am and 2:30 pm only on the above tender closing date.

There will not be a public tender opening. Registered Bidders will receive an email invitation to view the Tender Opening using Microsoft Teams software. Email invitations will be sent to the address provided on the Official Bidder's List. The Tender Opening Committee will conduct the evaluation of the tenders and Compliant tenders will be included in the summary of bids on the City's Tenders & Proposals website within 1 business day following the tender closing.

ADDITION TO THE SPECIFICATIONS

TO DIVISION 3 – PARTICULAR SPECIFICATIONS

Page 3-19, replace Clause 3.1.30.9 with the following:

3.1.30.9 Measurement For Payment – Dominion Park SLS Civil

The quantity to be measured for payment shall be by the lump sum. This includes the supply and transportation of all labour, materials and equipment, excavation and backfilling for the foundations, trucking material off site and stockpiling of material for re-use, shoring, dewatering trenches and excavations, dewatering of sanitary wastewater including the existing forcemain during tie-in, crushed rock or crushed gravel and pit run gravel for backfilling and under concrete, compaction, adjustments, thrust blocks, site work, flexible sealant, clean-up, and all work incidental thereto, all as specified or as shown on the drawings or as laid out by the Consultant.

The lump sum price for station construction shall also include the modification to the existing wet well consisting of the supply and transportation of all labour, equipment and material, excavation, trucking material off site and stockpiling of material for re-use, backfilling, shoring, dewatering, granular bedding material, compaction, new pre-cast concrete wet well cover and sections as required, modification of existing wet well benching to allow installation of new pumps, access hatch(s), frame and cover, gaskets, padlocks, insulation, flexible sealant, core drilling, pipe seal, leakage testing, adjustments, clean-up and all work incidental thereto, all as specified or as shown on the drawings or as laid out by the Consultant.

Page 3-19, add Clause 3.1.30.10:

3.1.30.10 Measurement For Payment – Dominion Park SLS Structural

The quantity to be measured for payment shall be by the lump sum. This includes the supply and transportation of all labour, materials and equipment, concrete form work, reinforced concrete work, concrete, foundation, lean concrete infill under foundations, rigid foundation wall insulation, installation of pipe penetration sleeves, fibreglass enclosure including all required insulation, strapping, doors and hardware, metal cladding and accessories, outside finishes, various exterior metal work stairs, railing and grating, paint, clean-up, and all work incidental thereto, all as specified or as shown on the drawings or as laid out by the Consultant.

Note: Signed copy of the addendum **must** be enclosed in the tender documents, according to the Instructions to Tenderers and Tendering Procedures in Division 2 of the Contract Specifications.

BY:


CHIEF CITY ENGINEER

CONTRACTOR'S SIGNATURE

TO BE SIGNED AND ATTACHED TO TENDER DOCUMENTS