

TRANSMITTAL SHEET

TO: All Bidders

DATE: January 24, 2024

TOTAL NUMBER OF PAGES (INCLUDING COVER PAGE): 6

FROM: Holly Young, P. Eng. TEL. #: (506) 658-4455
Utilities & Infrastructure Services

IF YOU DID NOT RECEIVE ALL PAGES, OR FURTHER INFORMATION IS REQUIRED,
PLEASE CONTACT THE SENDER

MESSAGE:

TENDER NO: 2023-13

St. Paul Street (Winter Street to End) -

Water, Sanitary and Storm Sewer Renewal and Street Reconstruction

Please find attached a copy of **Addendum #1** for the above tender.

As of March 2021, please be advised that an ***Acknowledgement Form*** (historically sent as part of the City's addendum packages) confirming receipt of an Addendum is **no longer** included in the addendum package.

However, in accordance with Section 2.5.03 of the City's General Specifications, it remains a requirement that **each Addendum** will contain a signature page(s) which each Tenderer is **required to sign and include with its Tender submission.**



UTILITIES & INFRASTRUCTURE SERVICES
 Engineering Services
 175 Rothesay Avenue
 Saint John, NB, E2J 2B4

ADDENDUM

PROJECT TITLE:

St. Paul Street (Winter Street to End) – Water, Sanitary and Storm Sewer Renewal and Street Reconstruction

ADDENDUM NO: 1

DATE: JANUARY 24, 2024

PAGE: 1 OF 5

TENDER NO: 2023-13

MAKE THE FOLLOWING MODIFICATIONS TO THE ABOVE PROJECT. INCLUDE IN THE AMOUNT OF THE TENDER ANY ADDITIONS TO OR DEDUCTIONS FROM THE COST OF THE WORK BY REASON OF THESE INSTRUCTIONS. THE DATE FOR RECEIVING TENDERS REMAINS AT: **2:30:00 PM, TUESDAY, JANUARY 30, 2024.**

ADJUSTMENTS TO THE SPECIFICATIONS

Division 2 – Submission of Tender

The City of Saint John is implementing adjustments to the tender submission procedure as follows:

Section 2.6.01 Location of Tender Box for the Submission of Tender

175 Rothesay Avenue, Saint John, New Brunswick

The tender box will be available at the main building entrance for submission of tenders by the Tenderer between the hours of 9:30 am and 2:30:00 pm only on the above tender closing date.

There will not be a public tender opening. Registered Bidders will receive an email invitation to view the Tender Opening using Microsoft Teams software. Email invitations will be sent to the address provided on the Official Bidder’s List. The Tender Opening Committee will conduct the evaluation of the tenders and Compliant tenders will be included in the summary of bids on the City’s Tenders & Proposals website within 1 business day following the tender closing.

ADJUSTMENTS TO DIVISION 4 - FORM OF TENDER

In the Contract Specifications, Division 4 – Form of Tender, Section 4.5 (Schedule of Quantities and Unit Prices) replace Sheet 8 of 17, Sheet 13 of 17, and Sheet 14 of 17 with the attached Sheet 8 of 13 (Addendum #1), Sheet 13 of 17 (Addendum #1), and Sheet 14 of 17 (Addendum #1).

Please see the following response to questions received:

Q1: *Street Signage - Would you mind providing the spec for the signs?*

A1: Please refer to the Tender Documents, Section 3, Appendix B.

Q2: *Are the majority of the storm services just getting capped off at the property line other than the lateral at 43 where there would be an actual connection at the property line. Just wondering if you know if there are existing draintile on the buildings we need to tie into / find at the property line.*

A2: Records indicate there are 2 existing storm laterals that the contractor would need to connect to. There are 2 proposed storm laterals to be installed and capped. Locations will be confirmed in the field during construction.

Q3: *Can the city review the asphalt quantities and adjust if need to reflect the actual scope of work more accurately?*

A3: Please refer to Sheet 14 of 17 (Addendum #1).

Q4: *There is a note on the drawings that mentions all existing capped laterals to be removed from the roadway unless otherwise directed by the engineer. I know the specifications mention that pipe removal outside normal limits will be paid under common excavation and imported gravel. I just want to confirm that removing the capped laterals will be paid through common excavation along with other pipe removal outside the pipe trenches.*

A4: Please refer to the Tender Documents, Section 3.1.18 Excavation Outside Normal Trench Limits.

Note: Signed copy of the addendum **must** be enclosed in the tender documents, according to the Instructions to Tenderers and Tendering Procedures in Division 2 of the Contract Specifications.

BY:



CHIEF CITY ENGINEER

CONTRACTOR'S SIGNATURE

TO BE SIGNED AND ATTACHED TO TENDER DOCUMENTS

DIVISION 4
SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2023-13
TITLE ST. PAUL STREET (WINTER STREET TO END)
WATER, SANITARY & STORM SEWER RENEWAL AND STREET RECONSTRUCTION

UNIT PRICE TO BE EITHER
 TYPEWRITTEN OR PRINTED IN
 INK IN WORDS AND PRINTED
 NUMERICALLY

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
h)	Adjust connections into manhole or catch basin due to obstacles, etc.		Each	1			
i)	Core drill opening into existing pre-cast manhole and connect new pipe		Each	1			
j)	100mm storm sewer lateral connections to main (incl. fitting and bends typ.)		Each	4			
k)	Connection of new 100mm Ø pipe to existing 100mm Ø pipe incl. coupling		Each	4			
l)	Connection of new 150mm Ø pipe to existing 150mm Ø pipe incl. coupling		Each	1			
m)	Connection of new 200mm Ø pipe to existing 200mm Ø pipe incl. coupling		Each	2			
n)	Connection of new 450mm Ø pipe to existing 450mm Ø pipe incl. coupling		Each	2			
o)	100 mm Ø PVC cap		Each	2			
3	<u>Insulation - Supply & Install</u>	11					
a)	Supply and install 50mm thick insulation		m ²	10			

DIVISION 4
SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2023-13 **UNIT PRICE TO BE EITHER TYPEWRITTEN OR PRINTED IN INK IN WORDS AND PRINTED NUMERICALLY**

TITLE ST. PAUL STREET (WINTER STREET TO END)
WATER, SANITARY & STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
F	ROAD WORK	13, 24					
1	<u>Excavation (Roads or Other Surfaces)</u> a) Common excavation - includes all road, driveways, sidewalks, and areas for regrading purposes b) Rock excavation		m ³	1150			
2	<u>Granular Backfill & Compaction (Roads or Other Surfaces) - Supply & Place</u> a) Imported Pit Run Gravel Subbase b) Imported Crushed Gravel Base Material	13, 24	m ³	560			
3	<u>Bituminous Tack</u> a) Supply & place bituminous tack	27	m ²	190			
4	<u>Asphalt Cold Milling - Removal of Existing Asphalt & Disposal at an Approved Location</u>	27	m ²	1300			
				288			

**DIVISION 4
SCHEDULE OF QUANTITIES AND UNIT PRICES**

CONTRACT NUMBER 2023-13

**UNIT PRICE TO BE EITHER
TYPEWRITTEN OR PRINTED IN
INK IN WORDS AND PRINTED
NUMERICALLY**

TITLE ST. PAUL STREET (WINTER STREET TO END)

WATER, SANITARY & STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
5	<u>Asphalt Concrete - Supply & Place</u> 27						
	a) Superpave 9.5 (0.3 to < 3 million ESALs)		t	130			
	b) Superpave 12.5 (0.3 to < 3 million ESALs)		t	200			
	c) Superpave 9.5 (0.3 to < 3 million ESALs) Miscellaneous Handwork		t	5			
6	<u>Calcium Chloride - Supply & Place</u> 24		Per 40 kg	15			
7	<u>Contingency</u>	2.6.03	LS	1	Twenty Two Thousand Dollars and Zero Cents	22,000.00	22,000.00
	AMOUNT "F" (ROAD WORK)						