

TRANSMITTAL SHEET

TO: All Bidders

DATE: October 24, 2024

TOTAL NUMBER OF PAGES (INCLUDING COVER PAGE): 6

FROM: Holly Young, P. Eng. TEL. #: (506) 658-4455
Utilities & Infrastructure Services

IF YOU DID NOT RECEIVE ALL PAGES, OR FURTHER INFORMATION IS REQUIRED,
PLEASE CONTACT THE SENDER

MESSAGE:

TENDER NO: 2023-18

**Carmarthen Street (Mecklenburg Street to Orange Street) -
Water, Sanitary and Storm Sewer Renewal and Street Reconstruction**

Please find attached a copy of **Addendum #1** for the above tender.

As of March 2021, please be advised that an ***Acknowledgement Form*** (historically sent as part of the City's addendum packages) confirming receipt of an Addendum is **no longer** included in the addendum package.

However, in accordance with Section 2.5.03 of the City's General Specifications, it remains a requirement that **each Addendum** will contain a signature page(s) which each Tenderer is **required to sign and include with its Tender submission.**



UTILITIES & INFRASTRUCTURE SERVICES
Engineering Services
175 Rothesay Avenue
Saint John, NB, E2J 2B4

ADDENDUM

PROJECT TITLE:

**Carmarthen Street (Mecklenburg Street to Orange Street) -
Water, Sanitary and Storm Sewer Renewal and Street
Reconstruction**

ADDENDUM NO:

1

DATE:

October 24, 2024

PAGE:

1 OF 5

TENDER NO:

2023-18

MAKE THE FOLLOWING MODIFICATIONS TO THE ABOVE PROJECT. INCLUDE IN THE AMOUNT OF THE TENDER ANY ADDITIONS TO OR DEDUCTIONS FROM THE COST OF THE WORK BY REASON OF THESE INSTRUCTIONS. THE DATE FOR RECEIVING TENDERS HAS BEEN EXTENDED TO: **2:30:00 PM, TUESDAY, NOVEMBER 5, 2024.**

ADJUSTMENTS TO THE SPECIFICATIONS

Division 2 – Submission of Tender

The City of Saint John is implementing adjustments to the tender submission procedure as follows:

Section 2.3 Schedule for the Tender Process

Please note that the tender closing date has been extended to 2:30:00 pm on Tuesday, November 5, 2024.

Section 2.6.01 Location of Tender Box for the Submission of Tender

175 Rothesay Avenue, Saint John, New Brunswick

The tender box will be available at the main building entrance for submission of tenders by the Tenderer between the hours of 9:30 am and 2:30:00 pm only on the above tender closing date. Tenderers shall maintain physical distancing from others when depositing their tender in the tender box.

There will not be a public tender opening. Registered Bidders will receive an email invitation to view the Tender Opening using Microsoft Teams software. Email invitations will be sent to the address provided on the Official Bidder's List. The Tender Opening Committee will conduct the evaluation of the tenders and Compliant tenders will be included in the summary of bids on the City's Tenders & Proposals website within 1 business day following the tender closing.

ADJUSTMENTS TO DIVISION 4 - FORM OF TENDER

In the Contract Specifications, Division 4 – Form of Tender, Section 4.5 (Schedule of Quantities and Unit Prices) replace the following sheets:

Sheet 10 of 17 with the attached Sheet 10 of 17;

Sheet 11 of 17 with the attached Sheet 11 of 17; and

Sheet 15 of 17 with the attached Sheet 15 of 17.

Please see the following response to a question received:

Q1: The drawings show a 3.0m separation between your water and sanitary lines which I would assume is to remain in accordance with the Section 805 in the AWWA Standards. We would like to know if you would allow us to reduce that horizontal separation, but increase the vertical separation from the invert of the water main to the top of the sanitary main to 0.45m and insulate over top of the water main with 2" rigid insulation.

A1: The design alignment shall remain as per the Tender drawings.

Note: Signed copy of the addendum **must** be enclosed in the tender documents, according to the Instructions to Tenderers and Tendering Procedures in Division 2 of the Contract Specifications.

BY:



CHIEF CITY ENGINEER

CONTRACTOR'S SIGNATURE

TO BE SIGNED AND ATTACHED TO TENDER DOCUMENTS

DIVISION 4

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2023-18

UNIT PRICE TO BE EITHER
TYPEWRITTEN OR
PRINTED IN INK IN WORDS
AND PRINTED
NUMERICALLY

TITLE: CARMARTHEN STREET (MECKLENBURG STREET TO ORANGE STREET)

WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
D	ADJUSTMENT OF STRUCTURES						
1	<u>Adjustment and Rebuilding of Manholes, Catch Basins and Valve Boxes</u>	12					
	a) Adjust top section to finish grade as required, using <u>existing</u> frame & cover including top 5 cm		Each	1			
2	Utility manhole adjustment. Adjust top section to finish grade as required, using existing frame and cover		Each	1			
3	<u>Contingency</u>	2.6.03	LS	1	One Thousand Dollars and Zero Cents	1,000.00	1,000.00
	AMOUNT "D" (ADJUSTMENT OF STRUCTURES)						

DIVISION 4

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2023-18

**UNIT PRICE TO BE EITHER
TYPEWRITTEN OR
PRINTED IN INK IN WORDS
AND PRINTED
NUMERICALLY**

TITLE: CARMARTHEN STREET (MECKLENBURG STREET TO ORANGE STREET)

WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
E	CONCRETE CURB AND SIDEWALK	23					
1	<u>Concrete Curb (Regular & Dropped) - Supply & Place</u> Concrete curb (regular & dropped). Excavation and backfill NOT included (Method "B")	23	m	330			
2	<u>Concrete Sidewalk - Supply & Place</u> a) 1.8m wide concrete sidewalk (Regular and dropped) NOT including excavation and backfill (Method "B") b) Variable width concrete sidewalk (Regular and Dropped) NOT including excavation and backfill (Method "B") c) Install 200mm thick concrete pad, locations to be determined in the field. Typical size 1.0m x 1.8m, including excavation & backfill	23	m m ² m ²	275 180 5			

DIVISION 4

SCHEDULE OF QUANTITIES AND UNIT PRICES

CONTRACT NUMBER 2023-18

UNIT PRICE TO BE EITHER
TYPEWRITTEN OR
PRINTED IN INK IN WORDS
AND PRINTED
NUMERICALLY

TITLE: CARMARTHEN STREET (MECKLENBURG STREET TO ORANGE STREET)

WATER, SANITARY AND STORM SEWER RENEWAL AND STREET RECONSTRUCTION

ITEM NO.	DESCRIPTION	DIV. NO.	UNIT	EST. QTY.	UNIT BID PRICE		TOTAL (\$)
					WRITTEN	NUMERICAL	
G	LANDSCAPING	26					
1	<u>Landscaping - Supply & Place</u>						
	a) Topsoil - 100mm thickness		m ³	34			
	b) Nursery Sod (minimum thickness 40mm)		m ²	345			
	c) Nursery Trees (min 50mm Ø trunk B&B) Supply and install 2000mm xx 1500mm x 900mm tree pit excavation, tree, backfill and topsoil.		Each	8			
2	<u>Driveway Reinstatement - Supply & Place</u>	24					
	a) Supply and place driveway stone to match existing.		m ³	20			
2	<u>Contingency</u>	2.6.03	LS	1		One Thousand Dollars and Zero Cents	1,000.00
	AMOUNT "G" (LANDSCAPING)						